



Energy Audit Report for Stockton St. Peter's Church



Site Address	Stockton St. Peter's Church, TS18 3PJ
Church Code	613319
Author	Tim Mawby Graduate Consultant
Date	13 th December 2019
Version	1.0

Contents

1	Executive Summary	3
2	Church Information.....	4
3	Energy Procurement Review.....	5
3.1	Electricity	5
3.2	Gas.....	5
4	Energy Usage Details	5
4.1	Cost & Consumption	5
4.2	Energy Benchmarking (Based on CofE Shrinking the Footprint – Energy)	5
5	Building Performance and Opportunities.....	6
5.1	Building Envelope	6
5.2	Heating System – Boilers	6
5.3	Heating System – Pipework and Distribution	7
5.4	Heating System – Heat Emitters	7
5.5	Hot Water System	8
5.6	Lighting	8
5.7	Renewables.....	8
6	Potential Saving Opportunities	9
7	Assumptions.....	9
7.1	Assumptions.....	9
7.2	Economic Life.....	9
7.3	Implementation.....	9
7.4	Cumulative Savings and Double Counting	10
8	Funding Sources	10
9	Faculty Requirements	10
10	Limitations	10

1 Executive Summary

An energy survey of St. Peter's Church, Stockton-on-Tees, TS18 3PJ was undertaken by ESOS Energy Ltd to provide advice to the Church on how it can be more energy efficient and provide a sustainable and comfortable environment to support its continued use. This audit has been provided in conjunction with 2buy2, the Church of England's Parish Buying scheme provider.

This energy audit has been undertaken by a suitably qualified and experienced energy auditor. Benefits of implementing the opportunities identified in this Report include a reduction in energy costs in the first instance, but could also reduce other costs, increase staff awareness and engagement, and improve comfort and staff satisfaction in the workplace.

The Church has a number of ways in which it can be more energy efficient. Our key recommendations have been summarised in the table below and are described in more detail later in this report. It is recommended that this table is used as the action plan for the church in implementing these recommendations over the coming years:

Energy Saving Measure	Annual Energy Savings (kWh)	Annual Cost Savings (£)	Estimated Capital Cost	Payback Period (Years)	Annual Carbon Savings (Tonnes CO ₂ e)
Install insulating lagging to exposed heating pipework (estimated 3% saving)	2,430	£101	£200	2.0	0.5
Replace or repair the sealing on the original church entrance pipework (estimated 5% saving)	4,050	£168	£100	0.6	0.8
Chapel – replace 25W CFLs with 3.5W LED alternatives.	564	£81	£120	1.5	0.2
Office – replace 4x58W fluorescent tubes with 22W LED alternatives.	629	£91	£160	1.8	0.2
TOTALS	7,673	£441	£580	1.3	1.7

The headline messages from the audit are:

- ▲ £580 investment in energy reduction measures would achieve an estimated annual saving of 7,673kWh (combined electric and gas).
- ▲ Based on current electricity and gas tariffs, this would result in an annual financial saving of £441.
- ▲ The simple payback period on this investment is 1.3 years.

The Church should check any faculty requirements with the DAC Secretary at the Diocese before commencing any works.

2 Church Information

A site survey was undertaken by Tim Mawby on Wednesday 13th November 2019. The survey was non-invasive (visual only) and entailed a general walk throughout the church areas, including back of house spaces and plant rooms.

Photograph 1: St Peter's Church External View



General Information	
Site Address	St Peter's Church Yarm Road Stockton on Tees TS18 3PJ
Listed Status	Unknown
Building Age	Built in 1881
Floor Area	655sqm
Usage	Typically 21 hours per week

3 Energy Procurement Review

Energy bills for gas and electricity have been supplied and have been reviewed against the current market rates for energy.

3.1 Electricity

Day Rate	14.44 p/kWh
----------	-------------

3.2 Gas

Rate	4.16 p/kWh
------	------------

The review has highlighted that there may be opportunities to gain environmental benefits from improved procurement of the energy supplies at this site.

We would therefore recommend that the Church obtains a quotation for its gas and electricity supplies from the CofE Parish Buying scheme (<https://www.parishbuying.org.uk/categories/energy/energy-basket>). This scheme only offers renewably sourced energy and therefore it is an important part of the process of making Churches more sustainable.

4 Energy Usage Details

4.1 Cost & Consumption

Energy Type	Annual kWh
Gas	97,188
Electricity	7,406

If not already in place, it is recommended that the Church consider asking their suppliers to install smart meters so that the usage can be monitored more closely, and the patterns of usage reviewed against the times the building is in use.

4.2 Energy Benchmarking (Based on CofE Shrinking the Footprint – Energy)

Energy Type	Size (Sqm)	Benchmark Energy Use (kWh/Sqm)	Actual Energy Use (kWh/Sqm)	Variance from Benchmark (%)
Gas	655	105	148	41%
Electricity	655	20	11	-45%

The building is using more gas than expected. The building is using less electricity than expected.

5 Building Performance and Opportunities

The building is well run with proactive onsite team in terms of energy conversation with some areas of improvement already being identified. The following sections will highlight where further improvements could potentially be made.

5.1 Building Envelope

From visual inspection, the majority of the building envelope appears to be in a reasonably good state of repair, however there is no roof or wall insulation. The building's original entrance was sealed shut; however the condition of the seal is deteriorating, leading to a draft entering the building. It is recommended that this is resealed.

Photograph 2: Sealed Entrance



5.2 Heating System – Boilers

Heating is provided to the church via 2no. Worcester combination boilers (installed in 2014) located in the basement plant room. The boilers are operated by a control panel situated in the vestry, where a timer has been set to turn the boilers on between 12:00 and 14:00. The boilers' controls allow for a manual override so that they can be switched on outside of these hours.

The existing boilers are well within their expected operating life, and so are not required to be replaced in the near future, however the client may wish to explore the possibility of installing an air to water heat pump heating system in order to move towards the goal of decarbonising energy consumption.

Photograph 3: Gas Combination Boilers



5.3 Heating System – Pipework and Distribution

Portions of heating system pipework in the basement plant room are entirely exposed. Where pipework is insulated, this is aging and in poor condition in parts. It is recommended that insulating lagging is installed to the exposed pipework, and existing pipework lagging be replaced to reduce heat loss into the plant room.

Photograph 4: Heating Pipework



5.4 Heating System – Heat Emitters

Heating to the church is served via 20no. cast iron radiators. These radiators are supplied by heating pipes running in floor trenches covered with grilles. Radiators are partially obstructed by furniture which limits the effectiveness of the heating. It is advised that items are removed from the immediate vicinity to allow for better heat convention in the space.

A range of portable plug-in heaters are also present throughout the building and are used to provide additional heating to the smaller rooms when required. This can be an ineffective, inefficient and poorly controlled means of providing space heating, and can easily be left on when unoccupied. It is recommended that a more permanent heating solution be provided to these spaces if and when heating upgrades are undertaken.

Photograph 5: Church Radiators



5.5 Hot Water System

Hot water is supplied to the building via a 2.5-litre local electric Heatrae Sadia Supreme point of use water heater. Hot water usage is considered to be nominal.

5.6 Lighting

There is no lighting control system, motion detectors or daylight dimming controls. All light fittings are controlled via manual on/off switches.

The range of light fittings throughout the church areas are detailed below:

Chapel

- ▲ Approximately 24no. 25W compact fluorescent lamps – recommended to be replaced with 3.5W LED alternatives.

Photograph 6: Compact Fluorescent Lamps



Office

- ▲ 4no. fluorescent panels (each containing 4no. 58W fluorescent tubes)– recommended to be replaced with 22W LED alternatives.

Photograph 7: Fluorescent Panels



5.7 Renewables

There are currently no renewables on-site. A free desktop survey can be carried out by a specialist solar installer to identify the possibility of installing solar PV panels.

6 Potential Saving Opportunities

As part of the assessment, we carry out a close inspection of M&E plant and their associated controls, with the aim of identifying any issues that have significant impact on energy consumption and correct building operation. We have reviewed the building and associated HVAC and lighting operations and identified the following potential energy conservation opportunities (ECOs), which should be investigated:

Category	Actions	Potential Annual Savings			Investment (£)	Simple payback (yrs.)
		Elec/Gas (kWh)	Cost (£)	(tCO ₂)		
Heating	Install insulating lagging to exposed heating pipework (estimated 3% saving)	2,430	£101	0.5	£200	2.0
Heating	Replace or repair the sealing on the original church entrance pipework (estimated 5% saving)	4,050	£168	0.8	£100	0.6
Lighting	Chapel – replace 25W CFLs with 3.5W LED alternatives.	564	£81	0.2	£120	1.5
Lighting	Office – replace 4x58W fluorescent tubes with 22W LED alternatives.	629	£91	0.2	£160	1.8
TOTAL ELECTRICITY SAVINGS		1,193	£172	0.4	£280	1.6
TOTAL GAS SAVINGS		6,480	£269	1.3	£300	1.1
GRAND TOTAL		7,673	£441	1.7	£580	1.3

7 Assumptions

7.1 Assumptions

- ▲ Costs excludes labour, installation and access which will require the confirmation of a specialist contractor.
- ▲ Average cost of electricity at 14.44p/kWh.
- ▲ Average cost of gas at 4.16p/kWh.
- ▲ Electricity carbon emission rate of 0.31598 kgCO₂/kWh.
- ▲ Natural Gas carbon emission rate of 0.20776 kgCO₂/kWh.

7.2 Economic Life

CIBSE Guide M Appendix 12.A1 gives the economic life of plant common plant items. After this time the maintenance and repair make it economic to replace the asset. There will be energy savings inherent in the new equipment and the need to meet the minimum requirements of the Building Regulations. Some capital plant has long payback periods, when based on energy efficiency alone, but these should be part of an asset replacement programme with only the 'additional' cost of higher than minimum required energy standards being used to calculate ROI.

7.3 Implementation

Reviews of Energy Projects and Initiatives are designed to provide a high-level indication of options available clients and will not constitute a recommendation for implementation. Pricing and potential savings are indicative values and will not constitute an offer.

7.4 Cumulative Savings and Double Counting

It should be noted that further investigation may rule out some measures as impractical, either physically or financially. Some measures are mutually exclusive and provide diminishing returns if implemented together. For example, if the lighting load is reduced through more efficient lighting, there will be an increase in the heat demand on boilers, as the new lights generate less heat.

Each energy conservation measure is assessed independently at this stage so that they can be fairly compared. An assessment of any overlap will be undertaken once any projects are selected for implementation.

8 Funding Sources

There are a variety of charitable grants for Churches undertaking works and a comprehensive list of available grants is available at:

<https://www.parishresources.org.uk/wp-content/uploads/Charitable-Grants-for-Churches-Nov-2019.pdf>

9 Faculty Requirements

It must be noted that all works intended to be undertaken should be discussed with the DAC at the Diocese.

Minor works can be undertaken without the need for consultation and would include changing of light bulbs within existing fittings, repair and maintenance works to heating and electrical systems and repairs to the building which do not affect the historic fabric.

Major works which can be undertaken without a faculty but must be consulted on with permission sought from the Archdeacon through the DAC. This includes works of adaptation (but not substantial addition or replacement) of heating and electrical systems and also the replacement of existing boilers so long as the same pipe work, fuel source and flues are used. It can also be used to replace heating controls.

All other works will be subject to a full faculty.

Works which affect the external appearance of the church will also require planning permission (but not listed building consent) from the local authority and this will be required for items such as PV installations,

10 Limitations

The recommendations contained in this Report represent ESOS Energy's professional opinions, based upon the information listed in the Report, exercising the duty of care required of an experienced Sustainability Consultant.

ESOS Energy obtained, reviewed and evaluated information in preparing this Report from the Client and others. ESOS Energy conclusions, opinions and recommendations have been determined using this information. ESOS Energy does not warrant the accuracy of the information provided to it and will not be responsible for any opinions which ESOS Energy has expressed, or conclusions which it has reached in reliance upon information which is subsequently proven to be inaccurate.

This Report was prepared by ESOS Energy for the sole and exclusive use of the Client and for the specific purpose for which ESOS Energy was instructed. Nothing contained in this Report shall be construed to give any rights or benefits to anyone other than the Client and ESOS Energy, and all duties and responsibilities undertaken are for the sole and exclusive benefit of the Client and not for the benefit of any other party. In particular, ESOS Energy does not intend, without its written consent, for this Report to be disseminated to anyone other than the Client or to be used or relied upon by anyone other than the Client. Use of the Report by any other person is unauthorised and such use is at the sole risk of the user. Anyone using or relying upon this Report, other than the Client, agrees by virtue of its use to indemnify and hold harmless ESOS Energy from and against all claims, losses and damages (of whatsoever nature and howsoever or whensoever arising), arising out of or resulting from the performance of the work by the Consultant.