



Jane White  
Church Warden  
St Gregory's Parish Church  
Stoke St Gregory  
Taunton  
TA3 6EH

21<sup>st</sup> October 2022

### QUOTATION

Dear Ms White,

Having received Steve Loveridge's email, please see below an adjusted summary of the works that you are needing to be carried out. Specifications are as follows:-

#### **Main pathways and Entrances to Church (Total Area pathway – 78m<sup>2</sup>)**

- Uplift all lias slabs from main pathway & stack all good slabs for re-use or potential sale. Remaining stone to be removed from site. Supply MOT Type 1 stone and build up a compacted stone sub-base.
- Install shuttering along sides of pathway where appropriate. Pathway width to remain at approx. 1.45m width. Supply concrete mix and lay in prepared areas to blend in with existing concrete pathways. Concrete to be approx. **100mm thick** minimum. Finish off top surface to match existing as close as possible.
- At two entrances of church, lay stone sub-base then using the best (previously stacked) paving slabs, lay slabs on a bed of mortar & point with mortar.

**Total Cost (Labour & Materials) £7,570 + VAT**

#### **Narrow Pathway (Back of Church) – (Total Area Pathway – 16m<sup>2</sup>)**

- Uplift existing stone & construct new concrete pathway as above with pathway at 0.6m width.

**Total Cost (Labour & Materials) £1,550 + VAT**

If you have any queries regarding any of the above, please get back to me.

Yours sincerely

.....  
**Nigel Roper**