



Estimate

2nd May 2025

CHURCH OF ALL SAINTS, KINGSTON SEYMOUR, SOMERSET

ROPE GUIDES

Attend the tower with our bellhanger and accurately survey the tower to take all required measurements.

Manufacture and install a circular steel rope guide, painted black, at the optimum height above the ringing chamber floor, building the cleated frame ends into the tower walls or bolting them to the tower walls with stainless-steel resin anchor fixings, depending on the type of masonry.

The guide is to consist of four separate steel channel bars spanning the tower north-south and between these, fit a formed steel channel ring of suitable diameter. To this, fit six rope bosses with brackets to suit the rope circle. Fit four vertical suspension rods to the ceiling/floor above.

Refit the existing bell ropes and leave the bells in good order for full-circle ringing.

For the sum of:

SIX THOUSAND AND FOURTEEN POUNDS
(£6,014.00)
Plus VAT

N.B.

These estimate figures are based on current prices and are therefore subject to fluctuation.

TERMS OF PAYMENT

- 1) Payment in full net 30 days when all is completed in the tower.

A FACULTY MAY BE REQUIRED BEFORE ANY WORKS COMMENCE

EXAMPLE



Circular rope guides (Steventon, Oxon.)